

July 8, 2014

**Town of Mendon
Mendon, Massachusetts**

ADDENDUM NUMBER 1:

**FOR THE
ASBESTOS ABATEMENT AT THE FORMER CHURCH BUILDING
LOCATED AT 29-31 NORTH AVENUE
MENDON, MASSACHUSETTS**

Add the Following to Section 00800: The Owner will provide water by a hose to the building. At no additional cost to the Owner, the contractor is required to provide toilets as all systems are not working.

Delete Appendix A and replace with the attached.

**APPENDIX A
CHART OF ACM**

Location	Material	Approximate Quantity
First Floor	Flooring Materials	2,850 SF
Alter Wall	Wall Demolition	900 SF
Exterior	Windows	31 Total

Specific Notes:

1. All quantities are approximate. It's the Asbestos Contractor's responsibility to inspect the site and confirm condition and quantities prior to the submission of his/her bid package.
2. Remove and dispose as ACM of all types of flooring materials, including but not limited to carpets, linoleum flooring, plywood, wood system, vinyl floor tiles, resilient baseboard, transition strips, leveling compound and mastic under all above items (Flooring Materials). Removal must be done which leave substrate smooth (in similar condition to that which existed prior to Mastic application). Use of Chemicals will be permitted.
3. Remove the wood platforms in the front and back of the alter wall and all Flooring Materials that found on-top and might be found underneath.
4. Demolish and dispose of the alter wall on both sides. Refer to the attached drawings for detailed scope.
5. Remove and properly dispose of all windows, including but not limited to screens, windows, panels, glass, frames, sash, casings, sills, fasteners, anchors, sealant, flashing and other related items. Remove and properly dispose of all caulking/debris found on the ground on the exterior of the building. Caulking was found to contain asbestos and assumed to contain >1ppm of PCB's.
6. Window removal will be performed at a later time to be coordinated with the general contractor at no additional cost to the owner.

